

INVITATION FOR BID: PAVING, MILLING, AND LINE STRIPING

Bid Proposal Form - Scope of Work

Battletown Drive from W. Main to Bel Voi Drive

Item Description	Estimated Qty/ Unit of Measure	Unit Price	Amount
Apply 1.5" of SM 9.5AL	Approximate length 500 feet		
Width of Roadway	Approximate width 24 feet		
Mill Tie-In Joints	9 (bidder must verify length (area marked with white paint))		
Stop Bars	1 (12' x 2' Thermo Burn Down)		
Re-establish shoulder	2' width compacted 21A or compacted millings (both sides of street)		
		Total \$	

Cameron Street from Page Street to First Street

Item Description	Estimated Qty/ Unit of Measure	Unit Price	Amount
Apply 1.5" of SM 9.5AL	Approximate Length 1,000 feet		
Width of Roadway	Approximate Length 22 feet		
Mill Curb Relief	Approximate Length 750 feet		
Mill Tie-In Joints	9 (bidder must verify length (area marked with white paint))		
Stop Bars	2 (12' x 2' Thermo Burn Down)		
Re-establish shoulder	2' width compacted 21A or compacted millings		
		Total \$	

First Street from E. Main to end of Town Maintenance

Item Description	Estimated Qty/ Unit of Measure	Unit Price	Amount
Apply 2" of SM 9.5AL	Approximate Length 3,300 feet		
Width of Roadway	Approximate Width 24 feet		
Mill Curb Relief	Approximate Length 1,400 feet		
Right Turn Arrow	1 (Thermo Burn Down) replace to match existing		
Left Turn Arrow	1 (Thermo Burn Down) replace to match existing		
Straight Arrow	1 (Thermo Burn Down) replace to match existing		
Stop Bars	1 (Thermo Burn Down) bidder to verify length		
Mill Tie-In Joints	5 (bidder must verify length (area marked with white paint))		
Double Yellow Line	Approximate length 3,250 feet		
Re-establish Stone Shoulders	2' width compacted 21A or compacted millings		
		Total \$	

Springsbury Road from Jack Enders Boulevard to South End of Town Maintenance

Item Description	Estimated Qty/ Unit of Measure	Unit Price	Amount
Apply 2.0" of SM 9.5AL	Approximate Length 1,350 feet		
Width of Roadway	Width varies (bidder must verify)		
Mill Curb Relief	Approximate Length 400 feet		
Mill Tie-In Joints	6 (bidder must verify length (area marked by white paint))		
Stop Bars	1 (12' x 2' Thermo Burn Down)		
Restripe Double Yellow Line	Approximate 1,350 feet		
Restripe White Lines	Approximate 2,220 feet		
Right Turn Arrows	2 (Thermo Burn Down) replace to match existing		
Re-establish Shoulder	2' width compacted 21A or compacted Millings		
Total \$			

Pickett Court

Item Description	Estimated Qty/ Unit of Measure	Unit Price	Amount
Apply 1.5" of SM 9.5AL	Approximate Length 250 feet		
Width of Roadway	Width varies bidder to verify		
Mill Tie-In Joints	8 (bidder must verify length (area marked by white paint))		
Stop Bars	1 (12' x 2' Thermo Burn Down)		
Crosswalk	1 (replace to match existing)		
Re-establish Shoulder	2' width compacted 21A or compacted millings		
Total \$			

Page Street from E. Main Street to Liberty Street

Item Description	Estimated Qty/ Unit of Measure	Unit Price	Amount
Apply 1.5" of SM 9.5AL	Approximate Length 780 feet		
Width of Roadway	Approximate Width 24 feet		
Mill Tie-In Joints	6 (bidder must verify length (area marked by white paint))		
Mill Curb Relief	Approximate 460 feet		
DO NOT ENTER road stencil	2 (24" x 24")		
Stop Bars	1 (12' x 2' Thermo Burn Down)		
Re-establish Stone Shoulder	2' width compacted 21A or compacted millings		
Total \$			

