

TOWN OF BERRYVILLE, VIRGINIA
Invitation for Bids
Paving, Milling, and Line Striping
IFB # 2025-03

Addendum 1
Issued June 12, 2025

SUBJECT: Scope Amendment

The Scope of Work has been amended in the following manner:

- **Freemont Court:** Required milling has been changed from 8' mill relief in cul-de-sac to a total mill of street section. Individual milled tie-in joints have been eliminated.

Approximate length of street is 560 feet
Street width varies
Bidders must verify information provided

- **Station Road:** Required shoulder establishment has been changed to the following:
 - o East side of street – to the supports of the guardrail, where present and 2' wide where there is no guardrail, with compacted 21A or compacted millings.
 - o West side of street – 4' wide with compacted 21A or compacted millings.

Approximate length of street is 1,050 feet
Bidders must verify information provided

Please find attached the following:

- Amended Scope of Work

Please note that:

- All changes must be verified by bidders.

Approved and Issued:



Keith R. Dalton, Town Manager

6/12/25

Date

Bidder Acknowledgement

I acknowledge that I have received and reviewed this IFB addendum.

Authorized Signature

Date

Springsbury Road from Jack Enders Boulevard to South End of Town Maintenance

Item Description	Estimated Qty/ Unit of Measure	Unit Price	Amount
Apply 2.0" of SM 9.5AL	Approximate Length 1,350 feet		
Width of Roadway	Width varies (bidder must verify)		
Mill Curb Relief	Approximate Length 400 feet		
Mill Tie-In Joints	6 (bidder must verify length (area marked by white paint))		
Stop Bars	1 (12' x 2' Thermo Burn Down)		
Restripe Double Yellow Line	Approximate 1,350 feet		
Restripe White Lines	Approximate 2,220 feet		
Right Turn Arrows	2 (Thermo Burn Down) replace to match existing		
Re-establish Shoulder	2' width compacted 21A or compacted Millings		
Total \$			

Pickett Court

Item Description	Estimated Qty/ Unit of Measure	Unit Price	Amount
Apply 1.5" of SM 9.5AL	Approximate Length 250 feet		
Width of Roadway	Width varies bidder to verify		
Mill Tie-In Joints	8 (bidder must verify length (area marked by white paint))		
Stop Bars	1 (12' x 2' Thermo Burn Down)		
Crosswalk	1 (replace to match existing)		
Re-establish Shoulder	2' width compacted 21A or compacted millings		
Total \$			

Page Street from E. Main Street to Liberty Street

Item Description	Estimated Qty/ Unit of Measure	Unit Price	Amount
Apply 1.5" of SM 9.5AL	Approximate Length 780 feet		
Width of Roadway	Approximate Width 24 feet		
Mill Tie-In Joints	6 (bidder must verify length (area marked by white paint))		
Mill Curb Relief	Approximate 460 feet		
DO NOT ENTER road stencil	2 (24" x 24")		
Stop Bars	1 (12' x 2' Thermo Burn Down)		
Re-establish Stone Shoulder	2' width compacted 21A or compacted millings		
Total \$			

Unit Pricing

Item Description	Unit of Measure	Unit Price	Amount
Apply 1.5 inches of SM 9.5AL	Square Yard		
Apply 2 inches of SM 9.5AL	Square Yard		
Mill Tie-In Joints	Square Yard		
Mill Curb Relief	Square Yard		
Double Yellow Line Striping with VDOT approved paint	1 Linear Foot		
White Line Striping with VDOT approved paint	1 Linear Foot		
Left Turn Arrow (Thermo Burn Down)	Meet VDOT standard for streets posted 25 MPH		
Right Turn Arrow (Thermo Burn Down)	Meet VDOT standard for streets posted 25 MPH		
Straight Arrow (Thermo Burn Down)	Meet VDOT standard for streets posted 25 MPH		
Stop Bars (Thermo Burn Down)	1 Linear Foot		
Stone Shoulders	1 Square Foot		
Crosswalks (Thermo Burn Down)	1 Linear Foot		
21A Compacted Stone			
Compacting Milling - Shoulder			
Base scratch coat	per ton		
		Total \$	